



ArcelorMittal

USINE DE DESVRES
RUE BIDET - B.P. 65 - 62240 DESVRES
Fax : 03/21/99/28/37
Téléphone : 03/21/99/28/00

TEST REPORT ISO 404/DIN 50049.3.1/NFA 00001/NF EN 10204-3.1

N°933/0625460 Page 1
A02 A09/A03

Mill's identification DV	GALVANIZED STEEL COIL ON HR SUBSTRATE ON HOT ROLLED SUBSTRATE		
	Sizes		
	Length B13 0,00	Width B12 1500,0	Thickness B11 1,500

GLOSSAIRE
CDC : CAHIER DES CHARGES

Inspection organism Métallurgie A05	Customer and/or consignee MUUGA LOGISTICS OU KOORMA 5A MUUGA 74004 ESTONIE A06	Customer's Order Nbr 12938/001 A07	Mill's Order Nbr FD93HTH003 000001 A08	Grade and technical specifications Quality : DX51D+Z Standard : DX51D+Z EN10346:2015 Coating : ZINC 275,0 G/M2 Treatment : e PASSIVATION Reference : DX51D+Z	Delivery condition CONFORME CDC B04 Treatment of test samples B05
				Spangle : MINIMISE Aspect : ASP B SELON NORME B01/B02	

Minimum																											
Maximum																											

Product identification	Heat number	P (1)	Net Weight	Longitudinal tensile test			Transverse tensile test			H R B	Roughness		Chemical analysis in % (* : product analysis)										Coating (4)						
				Ys	Ts	EL%	YS	TS	EL%		Ra	Peaks	C	Mn	P	S	Si	Al	Ti	Face avant			Face arrière						
				(2)	(2)	(2)	(2)	(2)	(2)		µm	(3)								Edge	Center	Edge	Aver.	Edge	Center	Edge	Aver.	Aver.	
B07 68809401	B08 8649089610	B09 7500		C11 C12 C13	C11 C12 C13	C11 C12 C13	C11 C12 C13	C11 C12 C13				C71 0,039	C72 0,180	C73 0,008	C74 0,0063	C75 0,010	C76 0,045	0,000											

(1) Location D : Head M : Middle F : Tail B09	(2)	(3) Suivant CDC C13	(4) En g/m2 Sauf rev.moy.final En g/m2 DF	(5) En N/mm2	We hereby certify that the above cited shipment was produced according to the technical specifications of the contract and that, with inspection and tests completed, it meets those specifications as well as all norms and standards referred to in the contract. Inspection of markings, surface, sizes : satisfactory. Bend test results are satisfactory.	Date 27/09/19 Receiving Ager E. BONNEVIE Z01	D01 D01 D01	270
--	-----	---------------------------	--	-----------------	--	---	-------------------	-----